

"Connect the network, unlock the corridor, strengthen the supply chain." NEXUS-WC NPC Strategic Freight Connectivity

NEXUS-WC NPC

STRATEGIC FEASIBILITY STUDY & NETWORK MASTER PLAN CAPE REGIONAL INLAND CONTAINER DEPOT (ICD) NETWORK

Document Reference: NEXUS-WC-NPC/ICD/FSMP/2026-01

Status: Executive Strategic Planning Document

Prepared for: NEXUS-WC NPC

Date: 22 July 2026

CONTENTS

Section	Subject
1	Executive Summary & Strategic Intent
2	Node Architecture & Regional Site Analysis
3	Port Decongestion Mechanisms & Operational Impact
4	Multi-Stakeholder Shared Value Ecosystem
5	Strategic SWOT & TOWS Analysis
6	Technical & Intermodal Infrastructure Specifications
7	Phased Implementation & Deployment Roadmap
8	Strategic Conclusion
9	Disclaimer & Document Status

1. EXECUTIVE SUMMARY & STRATEGIC INTENT

The Port of Cape Town, particularly the Cape Town Container Terminal at Ben Schoeman Dock, experiences recurring landside and operational pressure associated with seasonal agricultural export peaks, wind-related disruption and heavy truck congestion across the N1, N2 and Marine Drive corridors. The proposed response is an eight-node hub-and-spoke Inland Container Depot (ICD) / Dry Port Network across the Western Cape and Northern Cape hinterlands.

The network is designed to decentralise selected port functions, including customs clearance, empty-container staging, pre-trip inspection, reefer monitoring and consolidation. In doing so, the model establishes a “Virtual Port Gate”, allowing cargo to be processed and buffered closer to origin before scheduled rail block shuttles and short-haul drayage move containers into the port system.

Strategically, the model seeks to shift freight from fragmented long-haul road movements toward coordinated intermodal flows, improve cargo resilience during port disruption, protect cold-chain integrity and create a more predictable operating environment for transporters, exporters, rail and port stakeholders.

2. NODE ARCHITECTURE & REGIONAL SITE ANALYSIS

The proposed network comprises eight nodes aligned to major agricultural catchments, industrial zones and freight corridors. The original study identifies the following node configuration and indicative distances from the Port of Cape Town.

Node	Location	Distance	Primary Cargo / Function
BELLCON	Bellville	24 km	FMCG, retail imports, intermodal dry/reefer shuttles
ATLANTIS CITY	Atlantis SEZ	40 km	Industrial manufacturing, West Coast regional freight
DALCON	Dal Josafat, Paarl	70 km	Wine, stone fruit, table grapes, cold storage
HERCON	Hermon	100 km	Citrus, grains, regional agricultural inputs
WOCON	Worcester	112 km	Table grapes, citrus, wine, processed foods
CALCON	Caledon	120 km	Canola, grain, stone fruit, Overberg produce
KLAWCON	Klawer	280 km	Olifants River table grapes, citrus, minerals

KIMCON	Kimberley	950 km	Northern Cape citrus, pecan nuts, mineral ores

The node architecture directly links agricultural production zones, metropolitan freight demand, industrial areas and interprovincial corridors with the port through road and rail interfaces.

3. PORT DECONGESTION MECHANISMS & OPERATIONAL IMPACT

3.1 Virtual Port Gate

The proposed operating model changes the conventional flow from farm-to-port long-haul trucking and terminal queuing to farm/packhouse-to-ICD drayage followed by scheduled rail or dedicated shuttle movement into the port.

3.2 Off-Dock Staging and Buffering

- Regional ICDs receive, inspect, clear and hold containers closer to the production origin.
- Reefer cargo can remain on powered inland stacks while awaiting terminal readiness.
- Long-distance trucks are prevented from converging unnecessarily on Cape Town during periods of stack or vessel uncertainty.

3.3 High-Density Rail Consolidation

- A 50-wagon block train is identified in the source study as capable of replacing up to 50 heavy road haulers.
- Scheduled rail shuttles can remove significant numbers of long-haul truck movements from the N1, N2 and N7corridors.
- Demand is converted from unpredictable individual truck arrivals into scheduled, consolidated freight flows.

3.4 Off-Peak Night Shuttling

- BELLCON and ATLANTIS CITY are positioned as metropolitan staging buffers.
- Cargo can be held during peak metropolitan traffic and transferred during the proposed 22:00–05:00 off-peak window.

3.5 Weather-Disruption Shock Absorption

- Inland powered reefer capacity provides a buffer when high winds interrupt terminal ship-to-shore operations.
- Cargo can remain safely staged inland, reducing the secondary road congestion created by port disruption.

These mechanisms are central to the proposed network's role as a resilience layer around the Port of Cape Town.

4. MULTI-STAKEHOLDER SHARED VALUE ECOSYSTEM

Transporters and Trucking Companies

- Potential transition from one long, unpredictable daily round trip toward multiple short-haul shuttle loops.
- Lower exposure to port queue idling, with corresponding potential reductions in fuel, tyre, maintenance and vehicle-wear costs.
- Shorter regional routes can support improved driver welfare and compliance with driving-hour requirements.

Exporters, Farmers and Cargo Owners

- Local reefer staging supports cold-chain continuity.
- Inland buffering reduces exposure to missed stack windows caused by road and terminal congestion.
- The source study identifies inland staging as potentially less costly than ocean-terminal dwell penalties.

Port and Rail Operators

- Scheduled rail arrivals can flatten yard-demand peaks.
- Point-to-point shuttle operations can improve wagon utilisation and turnaround.
- The model provides a platform for collaboration with private rail operators under open-access freight-market reforms.

Municipalities and Communities

- Reduced heavy-vehicle pressure can help protect major road corridors.
- Road-to-rail modal shift can support lower transport emissions.
- ICD development can create regional employment in logistics, customs, equipment operation, reefer maintenance and related services.

The source study presents these outcomes as shared-value propositions across transporters, exporters, port/rail operators and communities. ■filecite■turn0file0■L195-L248■

5. STRATEGIC SWOT & TOWS ANALYSIS

STRENGTHS	WEAKNESSES
Strategic coverage of major agricultural catchments	High upfront CAPEX for rail sidings and reefer infrastructure
Dual-modal road/rail integration	Complexity of synchronising eight nodes
Potential reduction in port gate congestion and truck dwell	Dependence on rail reliability and asset availability
Cold-chain protection through inland reefer infrastructure	

The external opportunities identified include rail open-access reform, digital logistics integration, carbon-credit opportunities and public-private partnership funding. Threats include infrastructure vandalism, resistance from traditional long-haul operating models and agricultural-volume volatility.

TOWS Strategic Response

- SO: Partner with private Train Operating Companies, integrate ICD Yard Management Systems with the DigitalLogistics Planning Platform, and develop measurable carbon benefits.
- WO: Use PPP structures for capital-intensive infrastructure and maintain hybrid road-rail operating flexibility during rail-capacity ramp-up.
- ST: Maintain dual-modal flexibility and transition existing long-haul operators into contracted short-haul drayage roles.
- WT: Implement the network in phases, beginning with high-volume nodes, and provide energy resilience through solar PV and battery-backed microgrids.

These strategies are directly derived from the source study's TOWS matrix and recommended actions.

6. TECHNICAL & INTERMODAL INFRASTRUCTURE SPECIFICATIONS

The source study proposes a standardised infrastructure platform so that each ICD can function as a coordinated extension of the ocean-terminal ecosystem.

Infrastructure Domain	Executive Requirement
Rail	Minimum 600 m dual rail sidings capable of receiving full 50-wagon block trains without line breaking.

Yard	Heavy-duty reinforced concrete aprons designed for 80-ton axle loads; reach stackers and RTG capability.
Reefer	380V/440V three-phase reefer points, standby generation and rooftop solar support.
Cold-chain	100–300 high-output reefer plugs, with PTI testing capability.
Digital Gate	OCR gate readers, automated weigh-in-motion and real-time EDI feeds.
Systems	Yard Management System integrated with relevant terminal, shipping-line and DLPP data flows.

7. PHASED IMPLEMENTATION & DEPLOYMENT ROADMAP

Phase	Period	Priority Nodes	Strategic Focus	Key Deliverables
1	0–12 months	BELLCON, WOCON, DALCON	High-volume core anchors	Rail siding upgrades, 200 reefer plugs per node, night shuttle service, live DLPP integration
2	12–24 months	ATLANTIS CITY, CALCON, KLAWCON	Regional agricultural and industrial corridors	PTI bays, consolidation depots, expanded road-rail equipment
3	24–36 months	HERCON, KIMCON	Strategic feeder and interprovincial extension	Seasonal pop-up depots and full network synchronisation

The phased approach prioritises BELLCON, WOCON and DALCON before extending the network into the regional agricultural, industrial and interprovincial corridors.

8. CONCLUSION

The proposed eight-node Cape Regional ICD Network presents a structured intermodal response to recurring landside congestion, seasonal agricultural peaks and disruption at the Port of Cape Town. Its central proposition is to move selected port-adjacent activities inland, establish regional cargo buffers, consolidate freight into scheduled rail and shuttle movements, and use digital visibility to coordinate the network.

For NEXUS-WC NPC, the network should be treated as a strategic freight-system architecture rather than a standalone depot programme. The value proposition rests on integration: road

transport, rail, terminal operations, exporters, agricultural supply chains, digital logistics systems and regional infrastructure must operate as one coordinated corridor.

The source study's strategic conclusion is that inland virtual gates can reduce urban landside congestion, protect export cold-chain quality and support a more resilient freight network for Southern Africa.

Any investment decision should proceed through appropriate technical, commercial, environmental, legal, rail-access, land-use, customs, terminal-interface and financial due diligence before capital commitments are made.

9. NEXUS-WC MOTIVATIONAL PRINCIPLE

“Connect the network. Unlock the corridor. Strengthen the supply chain. Build the future together.” NEXUS-WC NPC.

Freight connectivity through collaboration, evidence, innovation and disciplined execution.

10. DISCLAIMER & DOCUMENT STATUS

This document is an executive strategic redraft of the uploaded feasibility-study source. It is intended for strategic discussion, stakeholder engagement, planning and further feasibility assessment. It does not constitute a final investment decision, engineering design, legal opinion, tax opinion, environmental authorisation, rail-access approval, customs determination, funding commitment or guarantee of operational or financial performance.

Distances, technical parameters, operating assumptions, performance benefits and implementation concepts reproduced from the source material remain subject to verification through site surveys, engineering studies, traffic and cargo-flow modelling, rail capacity assessments, market validation, regulatory approvals, environmental processes, commercial agreements and detailed financial modelling.

No statement in this document should be interpreted as creating a contractual obligation or representation by NEXUS-WC NPC or any third party unless separately approved and executed in writing by authorised representatives.Confidentiality and distribution should be managed in accordance with applicable law, contractual obligations and the intended stakeholder audience.

